BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of work: Desilting of SWD from Manjunatha Palace to MS Ramaiah North City in ward no. 06 Thanisandra Area.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	27541.18	Excavation for roadwork in all type of soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, triming bottom and side slopes, in accordance with requirements of lines, grades and cross section, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications.	cum	146.96	
2	2400.00	KSRRB 2008-8: Cleaning and grubbing including uprooting rank vegetation, grass, brush, shrubs, saplings and tress of girth upto 300mm by manual means, in area in light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable	sqm	6.48	
3	150.00	Hiring of pump for Dewatering using 3.5K1/hr capacity pump	hr	54.00	
4	152.00	Hiring of Hydraullic excavator 1 cum Bucket	hr	1220.10	

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

23.9.16
Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Bangalore 92

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

23/9